

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20794-00-00
Spot: NWSW Sec/Twnshp/Rge: 31-32S-28W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HALLOCK Well #: 1-31
County: MEADE Total Vertical Depth: 5725 feet

Operator License No.: 32416
Op Name: BRG PETROLEUM CORPORATION
Address: 7134 S. YALE STE 600
TULSA, OK 74136

CIBP Size: feet: 5400 WITH 2 SX CMT
PROD Size: 4.5 feet: 5725 WITH 250 SX CMT
SURF Size: 8.625 feet: 1470 WITH 550 SX CMT

AP/86⁰⁶

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/15/2005 11:00 AM
Plug Co. License No.: 31705 Plug Co. Name: H & K PLUGGING AND SALVAGE
Proposal Revd. from: H & K PLUGGING & SALVA Company: Phone: (806) 665-2550

Proposed Plugging Method: DISPLACE HOLE WITH 9.5# MUD, SET CIBP 50 FOOT ABOVE PERFS 20 FOOT CEMENT ON TOP, CUT AND PULL CASING, RUN TUBING TO 1570 FEET, PUMP 75 SACKS TAG AND 20 SACKS 60 TO SURFACE, WELD ON STEEL ID PLATE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: PARTIAL
Date/Time Plugging Completed: 02/16/2005 1:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

CIBP @ 5400' & 2 SX CMT. 1ST PLUG RAN 2 7/8" TUBING TO 1520'. PUMP 10 BBL GEL WATER & 50 SX CMT. NO CIRCULATION. WOC. NO CMT TO TAG. 2ND PLUG PUMPED 10 BBL GEL WATER & 50 SX CMT. NO CIRCULATION. SDON. WOC. 2/16/05: 3RD PLUG TAG CMT TOP @ 1354'. PULLED TUBING TO 598' & MIXED 25 SX CMT. 4TH PLUG PULLED TUBING TO 60' & MIX 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5572	5582		

RECEIVED
MAR 03 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY H&K PLUGGING. RECOVERED 3027' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE 3-4-05

INV. NO. 2005061235