

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21445-00-00
Spot: SENENW Sec/Twnshp/Rge: 31-9S-17W
3980 feet from S Section Line, 3230 feet from E Section Line
Lease Name: ADAM Well #: 2
County: ROOKS Total Vertical Depth: 1265 feet

Operator License No.: 30821
Op Name: HITSCHMANN, CRAIG DBA C & R OIL
Address: PO BOX 308
NATOMA, KS 67651

PROD Size: 4.5 feet: 1238 w/325 sxs cmt
SURF Size: 8.625 feet: 170 w/125 sxs cmt

41"

Well Type: SWD UIC Docket No: D20484.0 Date/Time to Plug: 10/20/2004 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CRAIG HITSCHMAN Company: C&R OIL Phone: (785) 885-4564

Proposed Plugging Method: Ordered out 125 sxs 60/40 pozmix - 10% gel - 600# hulls.
4 1/2" cemented top to bottom.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2004 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Dug out backside. Surface pipe full with cement.
Allied pumped 80 sxs 60/40 pozmix - 10% gel with 400# hulls.
Max. P.S.I. 900#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
1066	1086		

RECEIVED
FEB 16 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

2-16-05

INV. NO.

2005061188

Form CP-2/3

FEB 10 2005

BYE

WADOICED

WOODMAN & IANNITTI DRLG CO
104 S BROADWAY #1008 WICHITA, KS 67202
CONTR NATOMA DRILLING CO. CITY ROOKS

31-9-17W
#2 ADAM 1190' FNL & 190' FEL, NW/4

GEOL _____ FIELD GANOUNG

E NA _____ CM 9/24/81 CARD ISSUED 11/5/81 IP SWDW
CED HILL 1066-1086

+ 4 +
+ + +
+ + +

API 15-163-21,445

LOG	TOPS	DEPTH	DATUM
CED H		929	
B CED H		1090	
TD		1265	

8-5/8" 170/125sx, 4 1/2" 1238/325sx
NO DST'S REPORTED
MICT - CO, PF (CED H) 1066-1086,
SWDW - INJECTION RATE SATISFACTORY

NOTE: ORIG LOC WAS C W/2 SE NW;
WAS #1 'A' ADAM

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS