

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04966-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 29-20S-12W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: KOMAREK Well #: 3
County: BARTON Total Vertical Depth: 3495 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N. MARKET, STE 1130
WICHITA, KS 67202

PROD Size: 4.5 feet: 3495
SURF Size: 8.625 feet: 249

11359

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2005 9:00 AM
Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (620) 793-2222

Proposed Plugging Method: Ordered 650 sxs 60/40 pozmix - 10% gel - 1500# hulls.
Casing pushed in at 1157'.
Took impression block - could not drill through bad spot.
Perfed at 660' and 1128'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2005 10:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

02-24-2005
Log Tech shot a two shot perf at 660' and 1128'.
RIH with tubing to 1125' - pumped 50 sxs neat followed with 200 sxs 60/40 pozmix with 500# hulls mixed in. Left set two hours.
Pulled tubing to 700' - pumped 200 sxs 60/40 pozmix with 500# hulls mixed in.
Cement did not circulate to surface - left set overnight.
02-25-2005
RIH with tubing and tagged cement at 569'.
Pulled to 549' - pumped 190 sxs cement with 300# hulls to circulate cement out of backside.
Shut in backside - cement circulated out of head.
Pulled tubing and tied onto 4 1/2" casing with a swedge - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Used 650 sxs cement and 1300# hulls.

Perfs:

Top	Bot	Thru	Comments
3485	3488		

RECEIVED
MAR 04 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #20639 AND #20640.

Plugged through: TBG

District: 04

10

Signed _____

Pat Staab

(TECHNICIAN)

INVOICED

DATE 3-7-05

INV. NO. 2005061241

Form CP-2/3

MAR 01 2005

E K EDMISTON

#3 KOMAREK

29-20-12W

NW NW NW

Contr. E K EDMISTON

BARTON

County

E 1850 RBComm

Comp. 12-1-61

IP 25 BOPD/ARB

Tops	Depth	Datum
HEEB	3061	-1211
RR 1M	3184	-1334
LANS	3200	-1350
CONG	3439	-1589
ARB	3445	-1595
TD	3495	-1645

Casing
 8" 250
 5" 3495
 DST 3449-70/2 HRS, 60' GIP, 40' O, 30' OCM, 30' WTRY M, BHP 1300-360#
 DST 3470-85/30", 30' M, NO OIL, NO WTR, BHP 1280-360#
 DST 3485-95/2 HRS, 240' G, 85' O, 60' SL MDY O, 40' H OCM, 20' WTRY M, BHP 1300-1185#/20"
 PERF 12/3485-88: FU 900' OIH/12 HRS: SWB 2 1/2 BOPH: ACID 500: FU 835' OIH/12 HRS
 BATCHMAN POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

3310W1