

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04332-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 2-18S-14W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SPIERS Well #: 1
County: BARTON Total Vertical Depth: 3378 feet

Operator License No.: 7023
Op Name: KLIMA WELL SERVICE, INC.
Address: 610 WEST FRONT STREET
CLAFLIN, KS 67525

PROD Size: 5.5 feet: 3368
SURF Size: 8.625 feet: 125

\$109⁷⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2005 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE, INC. Phone: (620) 786-1031

Proposed Plugging Method: Ordered 550 sxs 60/40 pozmix - 10% gel - 800# hulls.
Emergency plug with rig over hole.
Casing leaks at 2600' - 1700' - 500' - 400'.
Lock set packer stuck in the hole at 3060'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/28/2005 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

RIH with tubing to 2980'. Allied rigged to tubing and pumped 75 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 2000' - pumped 40 sxs cement with 150# hulls mixed in.
Pulled tubing to 1538' - pumped 285 sxs cement with 350# hulls mixed in to circulate cement out of backside - shut in backside.
Pulled tubing to 1000' - pumped 85 sxs cement to circulate cement to surface.
Pulled tubing and tied onto 5 1/2" casing with a swedge and pumped 45 sxs cement. Max. P.S.I. 100#.
Pushed cement to surface on the outside of 8 5/8".
No shut in pressure. Used 530 sxs cement and 800# hulls.


RECEIVED
MAR 04 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #171179.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE

3-7-05

INV. NO.

2005061242

Form CP-2/3

MAR 01 2005

MURPHY OIL COMPANY

#1

SPIERS

2-18-14W
SW SW SE

Contr. LEWIS DRILLING COMPANY

BARTON

County

E 1891 RB Comm.

Comp.

2-22-52

IP

203 BOPD (ARB)
PHY POT

Tops	Depth	Datum
LANS	3138	-1247
CONG	3342	-1451
ARB	3368	-1477
T.D.	3378	-1487

Casing

5" 3368

5 GOPH

BOYD POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECORDED
INDEXED