

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00528-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 31-5S-20W  
3630 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: PINKERTON Well #: 16  
County: PHILLIPS Total Vertical Depth: 3662 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 5.5 feet: 3662 150 SX CMT  
SURF Size: 8.625 feet: 196 250 SX CMT

# 119<sup>02</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/22/2005 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: RIC HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 689-7567

Proposed Plugging Method: Ordered 350 sxs Mid-Con lite and 600# hulls.  
Perf casing at 1150' and 1750'.  
Casing leak at 825'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/22/2005 1:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 3600'.  
Spotted 70 sxs cement with 300# hulls - (38 bbls slurry).  
Pulled tubing to 1600'.  
Spotted 90 sxs cement with 200# hulls (51 bbls slurry).  
POOH with tubing.  
Squeezed casing with 50 sxs cement to Max. P.S.I. 500#.  
Rigged up cementers to annulus and squeezed with 30 sxs cement with 100# hulls.  
Max. P.S.I. 100#.

Perfs:

Top	Bot	Thru	Comments
3642	3646		
3620	3633		

RECEIVED  
MAR 04 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Dennis J. Hamel  
(TECHNICIAN)

INVOICED

DATE 3-7-05  
INV. NO. 2005061243

Form CP-2/3

MAR 01 2005

CITIES SERVICE OIL CO. # 16 PINKERTON 31-5-20W  
 NE SW NE  
 Contr. R. W. BINE DRILLING CO. PHILLIPS County  
 E. 2216 Comm. Comp. 10-28-49 IP 182 BOPD

Tops	Depth	Datum
AN 4		+ 472
HEEB	3314	- 1128
LANS	3387	- 1171
B/KC	3583	- 1367
REAG	3623	- 1407
QTZ	3661	- 1445
T.D.	3662	- 1446

Casing  
 8" 196 PERF 3642-46  
 5" 3662 PERF 59S, 3620-33  
 2350' 01H/17 HRS  
 PMP 105 BQ/44 HRS


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

0300WMI  
 0716  
 0716