

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23712-00-00
Spot: E2NENE Sec/Twnshp/Rge: 9-15S-18W
4620 feet from S Section Line, 330 feet from E Section Line
Lease Name: DINGES Well #: 1
County: ELLIS Total Vertical Depth: 3680 feet

Operator License No.: 31925

PROD Size: 5.5 feet: 3677 125 sx cmt

Op Name: QUALITY WELL SERVICE, INC.

SURF Size: 8.625 feet: 1215 425 sx cmt

Address: 401 WEST MAIN
LYONS, KS 67554

#11960

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/17/2000 11:30 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (316) 278-2026

Proposed Plugging Method: Order 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug while pulling casing.

Plugging Proposal Received By: HERB DEINES

Witness Type: NONE

Date/Time Plugging Completed: 01/17/2000 1:30 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

Sanded to 3470' and spotted 5 sxs cement on sand with dump bailer.
Shot casing loose at 2742' and pulled to 1900'.
Mixed and pumped 130 sxs cement with 300# hulls.
Pulled casing to 1225' and pumped 50 sxs cement with 100# hulls.
Pulled casing to 425' and pumped 75 sxs cement with 100# hulls.
Pulled casing and topped with 10 sxs cement.

RECEIVED
MAR 04 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #2209.

Plugged through: CSG

District: 04

Signed

[Signature]
INVOICED

(TECHNICIAN)

DATE

3.7.05

*INV. NO.

2005061244

Form CP-2/3

MAR 01 2005

DAMAR RESOURCES, INC.
P. O. BOX 70


9-15-18W
C E/2 NE NE

HAYS, KS 67601
CONTR EMPHASIS OIL OPERATIONS

NOTICED

CITY ELLIOTT

GEOL _____ FIELD DINGES



ELV 2031 KB SPD 11/23/83 CARD ISSUED 2/24/84 IP P 40 BOPD & WTR
ARB 3643-3646

LOG	Tops	Depth/Datum
ANH	1208 + 823
B/ANH	1242 + 789
TOP	2997- 966
HEEB	3280-1249
TOR	3298-1267
LANS	3335-1304
BKC	3556-1525
ARB	3640-1609
RTD	3675-1644

API 15-051-23,712
 8 5/8 " 1215/425 SX; 5 1/2 " 3673/125 SX
 DST (1) 3343-85 (LANS) / 60-45-30-45, REC 720' MCW, SIP
 656-656#, FP 67-277 / 277-336#
 DST (2) 3554-3641 (PENN, ARB) / 60-45-30-45, REC 20' MUD,
 SO, SIP 117-117#, FP 50-58 / 58-72#
 DST (3) 3553-3649 (PENN, ARB) / 60-45-30-45, REC 90' MUD,
 60' OCM, SIP 1041-1041#, FP 67-101 / 101-117#
 MICT - CO, PF (ARB) 3643-46, AC 450 G, SWB 5 BFPH (98%
 OIL), FU 1150' FL (1000' OIL)/14 HRS, POP, P 40 BOPD & WTR
 12/23/83

RECEIVED

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS