

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA, KANSAS 67202

FORM CP-1

15-029-20003-00-00

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1970
CONSERVATION DIVISION
Wichita, Kansas

8-10-70

Lease Owner Mattson & Thompson c/o Don L. Thompson

Address P.O. Box 20151, Dallas, Texas 75220

Lease (Farm Name) Holbert #1 Well No. 1

Well Location C NW/4 NE/4 Sec. 33 Twp. 6 Rge. 4 (E) (W)

County Cloud Field Name (If Any) _____

Total Depth 3887 Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Well Log filed with application _____ or Well Log filed with Plugging Supervisor _____

Log attached hereto . . .

Date and hour plugging is desired to begin _____

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of company representative in charge of plugging operations _____

Address _____

Plugging Contractor Blackstone Drilling, Inc. License No. _____

Address P.O. Box 455, McPherson, Kansas 67460

Invoice covering assessment for plugging this well should be sent to Mattson & Thompson


c/o Don L. Thompson Address P.O. Box 20151, Dallas Texas 75220

and payment will be guaranteed by applicant.

MATTSON & THOMPSON

Signed: BY: Don L. Thompson
Applicant or Acting Agent

Date: July 20, 1970



15-029-20003-00-00

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

July 20, 1970

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1970
CONSERVATION DIVISION
Wichita, Kansas

8-10-70

COMPANY: HATTSON & THOMPSON
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 LEASE: HOLBERT #1
 LOCATION: C NW NE 33-6-4
 Cloud County, Kansas
 COMMENCED: July 10, 1970
 COMPLETED: July 19, 1970
 ELEVATION: 1579 K. B.

0	to	55	Line
55	to	190	Shale
190	to	250	Coal
250	to	265	Line
265	to	510	Shale & Red Bed
510	to	635	Lime & Shale
635	to	1855	Shale & lime
1855	to	2540	Lime & Shale
2540	to	2695	Line
2695	to	2925	Lime & Shale
2925	to	3052	Shale
3052	to	3158	Mississippi
3158	to	3219	Line
3219	to	3338	Shale
3338	to	3490	Line
3490	to	3570	Lime & Shale
3570	to	3750	Line
3750	to	3778	Sand
3778	to	3887	Line
		3887	T. D.

Cut 1 1/4 in. hole to 265 ft. and run 268 ft. of 8 5/8 in. surface pipe, cemented with 200 sacks at 265 ft. Plug down at 5:00 P. M., July 10, 1970. Cut 7 7/8 in. hole to 3887 ft. Hole dry and abandoned. Set bottom plug at 250 ft. and filled with 25 sacks of cement. Top plug at 40 ft. and filled with 10 sacks of cement. 2 sacks in rat hole. Plugged down at 12:00 Noon, July 19, 1970. Plugging completed by Gilbert Toman, State Plugger, Holyrood, Kansas.


TOPS: CERTY - 364' TANKIE - 1890' TOPEKA - 2040' LANSING - 2415'
 BASE KANSAS CITY - 2752' CHEREKKEE - 2887' MISSISSIPPI - 3052'
 KINDERHOOK - 3219' HUNTON - 3310' MAQUOKETA - 3509' VIOLA - 3589'
 SIMPSON - 3745' ARBUCKLE - 3869'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Holbert #1, located on the C NW/4 NE/4, Sec. 33-6-4, Cloud County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe, President



Johnnie L. Scheidt - Notary Public

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas of July, 1970.

Commission Expires: June 27, 1973.

State of Kansas



15-029-20003-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

July 22, 1970

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Holbert
Description	C NW NE ³³ 36-6-4W
County	Cloud
Total Depth	3887
Plugging Contractor	Blackstone Drilling


Mattson & Thompson
Box 20151
Dallas, Texas 75211

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,


J. Lewis Brock, Administrator

Mr. Gilbert Toman Box 180 Holyrood, Kansas
is hereby assigned to supervise the plugging of the above named well.