

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23027-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 8-8S-22W
940 feet from S Section Line, 390 feet from W Section Line
Lease Name: RICE TRUST D Well #: 1-8
County: GRAHAM Total Vertical Depth: 3620 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: P.O. BOX 1469
PLAINFIELD, IL 60544

SURF Size: 8.625 feet: 217

117⁶⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/06/2005 8:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 03/06/2005 10:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 1775' w/25 sxs.
2nd. Plug at 925' w/100 sx.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.


RECEIVED
MAR 14 2005
KCC WICHITA

Remarks: ACID SERVICES, INC.

Plugged through: DP

District: 04

Signed _____


(TECHNICIAN)

INVOICED

DATE 3-14-05

INV. NO. 2005061279

Form CP-2/3

MAR 07 2005