

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-12619-00-00  
Spot: NENENE Sec/Twnshp/Rge: 22-21S-12W  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: TAYLOR Well #: 1  
County: STAFFORD Total Vertical Depth: 3550 feet

Operator License No.: 31647 PROD Size: 5.5 feet: 3550  
Op Name: CHURCHHILL, KIM DBA K.C. OPERATI SURF Size: 8.625 feet: 304  
Address: 534 S E 70 AVE.  
ELLINWOOD, KS 67526

*#115 38*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2005 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BOTTOM TO 3190'. PLUG AT 640' WITH 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/07/2005 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3182' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 640' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3242			

RECEIVED  
MAR 15 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1700' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

*Stephen J. Pappas*  
(TECHNICIAN)

INVOICED

DATE 3-15-05

INV NO. 2005061283

*From C12/3*