

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01949-00-00

Spot: SESESE

Sec/Twnshp/Rge: 25-18S-8W

330 feet from S Section Line,

330 feet from E Section Line

Lease Name: LANSING J R

Well #: 13

County: RICE

Total Vertical Depth: 3262 feet

Operator License No.: 31389

PROD Size: 5.5 feet: 3261

Op Name: NOBLE PETROLEUM, INC.

SURF Size: 8.625 feet: 310

Address: 3101 N. ROCK ROAD, STE 125
WICHITA, KS 67226

#106 02

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/08/2005 10:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Sand perms to 3110' and put 5 sxs cement on top; cut off 5-1/2"; pull to 1050'; pump 35 sxs; pull to 700'; pump 35 sxs; pull to 360'; and circ cement to surf.
Plugging Method:

RECEIVED
KCC DISTRICT #2

MAR 8 - 2005

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: NONE

WICHITA, KS

Date/Time Plugging Completed: 03/08/2005 12:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3110' and put 5 sacks of cement on top. Cut off 5-1/2" at 1405'. Pulled to 1050' and pumped 35 sacks of cement with 150 lbs of cotton hulls. Pulled casing to 700' and pumped 35 sacks of cement with 150 lbs of cotton hulls. Pulled to 360' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #20644

Perfs:

Top	Bot	Thru	Comments
3169	3190		

RECEIVED
MAR 15 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE 3-15-05
INV. NO. 2005061287

Form CP-2/3