

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10367-00-01
Spot: NENESW Sec/Twnshp/Rge: 5-33S-42W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: RAMSEY Well #: 1-5
County: MORTON Total Vertical Depth: 3385 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 3200 FIRST PLACE TOWER
TULSA, OK 74103

CIBP Size: feet: 2540 WITH 2 SX CMT 01
PROD Size: 5.5 feet: 3379 WITH 200 SX CMT
SURF Size: 8.625 feet: 600 WITH 300 SX CMT 4110

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/07/2005 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2540' & 2 SX CMT. PLUG AT STUB WITH 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2005 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ SET AT 2540' WITH 2 SX CMT. 1ST PLUG PULL OUT OF HOLE TO 650'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 350'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2905	3158		
2730	2737		
2691	2693		
2681	2684		
2672	2678		

RECEIVED
MAR 15 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 717' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 3-15-05
INV. NO. 2005061286