

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00039-00-02
Spot: S2S2NE Sec/Twnshp/Rge: 26-33S-34W
2970 feet from S Section Line, 1320 feet from E Section Line
Lease Name: L C SCHMITT Well #: 1
County: SEWARD Total Vertical Depth: 6535 feet

Operator License No.: 6120
Op Name: CABOT OIL & GAS CORPORATION
Address: 600 17TH ST., SUITE 900 NORTH
DENVER, CO 80202

CIBP Size: feet: 1525
PKR Size: feet: 913
PROD Size: 7 feet: 2648 WITH 650 SX CMT
SURF Size: 10.75 feet: 574 WITH 800 SXCMT

#212³⁹

Well Type: SWD UIC Docket No: D08467.0 Date/Time to Plug: 12/27/2004 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & FILL WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2005 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 200# HULLS WITH 35 SX CMT. COULD NOT PULL FIBERGLASS TUBING OUT OF BAKER MODEL D PACKER @ 913'. RUN IN HOLE WITH SHOT CAN, SHOOT 2 3/8" FIBERGLASS TUBING OFF AT 900'. PUMP BOTTOM PLUG. HOLE CIRCULATED. PULL OUT OF HOLE WITH TUBING TO 600'. LOAD HOLE. START CMT. CMT CAME TO SURFACE AFTER 8 SX. HOLE IN TBG. TUBING PLUGGED. PULL OUT OF HOLE WITH REST OF FIBERGLASS TUBING. SHUT DOWN. 3/4/05: DRILLED OUT 7" CASING TO 830'. RUN IN HOLE WITH 2 3/8" TUBING TO 815'. LOAD HOLE & PUMP 20 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE WITH TUBING TO 600'. LOAD HOLE & PUMP 43 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE WITH TUBING TO 30'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
1150	1170		

RECEIVED
MAR 15 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 3-15-05
2005061782

For: