

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19095-00-00
Spot: S2NWSE Sec/Twnshp/Rge: 16-11S-19W
1650 feet from S Section Line, 1980 feet from E Section Line
Lease Name: WILES Well #: 4
County: ELLIS Total Vertical Depth: 3506 feet

Operator License No.: 5363

PROD Size: 5.5 feet: 3502 200 SX

Op Name: BEREXCO, INC.

SURF Size: 8.625 feet: 1280 575 SX

Address: PO BOX 20380
WICHITA, KS 67208

113⁹⁵

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/03/2005 10:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: DENNIS KIRMER

Company: BEREXCO, INC.

Phone: (620) 628-6101

Proposed
Plugging
Method:

Ordered out 50 sxs Common with 2% cc - 425 sxs 60/40 pozmix - 10% gel - 700# hulls.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/04/2005 12:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

03-03-2005

MIRU TIH with tubing to 3430' and spotted 50 sxs Common with 2% cc and 200# hulls.
POOH. Shot casing loose at 1946' and POOH.

03-04-2005

TIH with tubing to 1885' - tied onto and mixed 120 sxs with 500# hulls.
Pulled up to 1250' and spotted 100 sxs cement.
Pulled up to 750' and circulated cement with 115 sxs cement.
POOH. Hole full of cement.

RECEIVED
MAR 14 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE

3-14-05


INV. NO.

2005061270

Form CP-2/3

MAR 08 2005

1-35 MAP NO. _____ SEC. 16-11S-19W
 STATE Kansas COUNTY Ellis LOC. C S/2 NW SE
 OPER Okmar Oil Company, Wichita, Kansas FT./FR. _____ LINE
 WELL #4 FARM Wiles FT./FR. _____ LINE
 ZONE Sessin, West ELEV 1963 GR. 1965 DF 1967 KB
 CONT. Leben Drlg. Co. GEOL. Harold McNeil
 UNIT PTD 3500' Arb. test
 DATE 10-12-64 SPUD 10-7-64 COMP 11-3-64
 DEPTH 3506 FM Arb. PBTD
 PRODUCING FM. FROM — TO PERF W/HOLES TREATMENT
 Arb 3502 - 3506 OH 500A
 Co. P 25 BOPD
 8-5/8" @1280' w/550 Sx...
 5" @3502' w 200 Sx



Data Inc.

B Spl Tops :

Anh	1263 / 704	DST #1(Tor)3157-85, Op 1 hr, R 65' VHOCM,
Hb	3151 -1184	ISIP 1020#/30', IFP 40#, FFP 60#, FSIP
Tor	3170 -1203	250#/30'.
Lans	3190 -1223	DST #2(Lans)3183-3210, Op 1 hr, R 10' M,
Cgl	3438 -1471	ISIP 100#/30', IFP 0#, FFP 0#, FSIP 0#/30'
Arb	3501 -1534	DST #3(Lans)3340-3400, Op 1 hr, R 15' M,
		ISIP 740#/30', IFP 0#, FFP 0#, FSIP 380#
RTD	3503 -1536	/30'.
DDTD	3506 -1539	RTD 3503', No log, 5" @3502' w/200 Sx.
MICT, CO & DD 3506' TD (Arb)500A, § 1d, § 5 BOPH - NW/NT, POP,		
Co. P 25 BOPD, Gr. NA, Arb. 3502 - 06, COMPLETED		

MAGNET

1140