

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20235-00-00
Spot: SENE SW Sec/Twnshp/Rge: 23-20S-12W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KRUEGER B Well #: 1
County: BARTON Total Vertical Depth: 3360 feet

Operator License No.: 31647

PROD Size: 5.5 feet: 3353 w/100 sxs cmt

Op Name: CHURCHHILL, KIM DBA K.C. OPERATI

SURF Size: 8.625 feet: 225 w/220 sxs cmt

Address: 534 S E 70 AVE.
ELLINWOOD, KS 67526

\$109²⁰

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/04/2005 8:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: JOE MAES

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed
Plugging
Method:

Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.
Casing parted at 585'.

Plugging Proposal Received By: HERB DEINES

WitnessType: NONE

Date/Time Plugging Completed: 03/04/2005 10:30 AM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Sanded off bottom to 3300' and topped with 5 sxs cement using a dump bailer.
MIRU to pull casing - parted at 585'.
TIH with mill - could not make any hole - decided to P&A.
RIH with tubing to 585' - mixed and circulated cement with 195 sxs cement with 300# hulls.
POOH and swaged onto 8 5/8" - pumped 45 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 275#.

RECEIVED
MAR 14 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 3-14-05

INV. NO. 2005061271

Form CP-2/3

MAR 08 2005

ALPINE OIL & ROYALTY CO. INC #1 KRUEGER 'B' 23-20-12W
 WICHITA, KS SE NE SW

Contr. GABBERT-JONES, INC City. BARTON

Geol. DON MALONE Pool UNNAMED POOL

E. 1810 KB Cm. 5/10/68 Cp. 7/11/68 IPP 78 BOPD, NW
 API 15-009-20,235 ARB 3361-56

LOG Tops	Depth	Datum	Csg.
npa Base		+1230	8" 225/220 sx, 5" 3353/3005
HEEB	2989	-1179	DST 3160-3200/40", 101 MD/VEP
BRLM	3115	-1305	SLI SHO OIL, BHP 78-69#/30"
LANS	3130	-1320	FP 52-61#, TEMP 108
BKC	3315	-1505	DST 3249-72/75", 30 MD, BHP 242
ARB	3351	-1541	156#/30", FP 61-69#, TEMP 108
LTD	3353	-1543	DST 3345-60/1", 2400 GSP, 15240
RTD	3360	-1550	OIL, BHP 865/50"-848/45" =
			52-294#, TEMP 110
			CO, PF 3351-56, A 500, BU 1506
			OIL, SWB 45 BO, 500 OB, 742 OPS
			POP, .

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

WICHITA