

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01774-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 25-10S-21W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: HERROLD Well #: 3  
County: GRAHAM Total Vertical Depth: 3741 feet

Operator License No.: 31822  
Op Name: JOLEN OPERATING COMPANY  
Address: 100 N. BROADWAY, STE 2460  
OKLAHOMA CITY, OK 73102

PROD Size: 5.5 feet: 3717 125 SX CMT  
SURF Size: 8.625 feet: 202 150 SX CMT

# 12158

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/03/2005 12:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: PERRY S HENMAN Company: JOLEN OPERATING COMPANY Phone: (785) 625-9448

Proposed Plugging Method: Ordered out 350 sxs Swift Multi-Density Cement with 600# hulls.  
Arb. Production 3700' - 3741' open hole - pumping and in packer at 1565'.  
Unable to release packer - backed tubing off at 1565'  
Squeezed 1050' w/250 sxs on Oct 03, 1953.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/03/2005 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Tubing at 1565'. Swift Services pumped 100 sxs Swift Multi-Density cement neat - no circulation.  
Pumped 150 sxs SMD with 450# hulls - circulated cement.  
PTOH. Swift squeezed with 60 sxs SMD and 150# hulls.  
Max. P.S.I. 700#. S.I.P. 400#.  
Hooked up to backside - Instant 500#.

Perfs:

Top	Bot	Thru	Comments
1050	1635		

RECEIVED  
MAR 11 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 3-14-05

INV. NO. 2005061273

MAR 09 2005

ANDERSON-PRICHARD

#3

HERROLD

25-10-21W

22

NW SW NW

Contr. GLEN W PEEL

GRAHAM

County

E 2132 RB Comm. Comp. 4-24-53 IP 60 BOPD

Tops	Depth	Datum
ANH	1620	512
TOP	3156	-1024
HEEB	3360	-1228
TOR	3385	-1253
LANS	3403	-1271
SIMP	3703	-1571
ARB	3709	-1577
TD	3715	-1583

Casing

8" 202

5" 3710

DP, CO 3713, 1 1/2 BOPH/4

HRS: DD 3715, 1 1/2 BOPH/

7 HRS

ACID 250, SWB 3 BOPH/10

HRS: PMP 63 BO, NO WTR/

17 HRS

WHITE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

INDEXED