

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05981-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 29-11S-17W
330 feet from S Section Line, 1980 feet from E Section Line
Lease Name: GLATHART Well #: 3
County: ELLIS Total Vertical Depth: 3651 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 4.5 feet: 3628
SURF Size: 8.625 feet: 1250

A 118' 6"

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2005 12:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-9633

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 600'. PBTD 3400'. Drilling mud.
Prior squeeze job 3393' - 1760'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2005 6:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2790'. Allied pumped 120 sxs 60/40 pozmix - 10% gel with 400# hulls.
Pulled to 1250'. Allied pumped 265 sxs cement with 200# hulls.
Cement circulated out 8 5/8" and 4 1/2" casing.
PTOH. Squeezed with 15 sxs cement.
Max. P.S.I. 600#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3628	3651	OH	
3605	3610		

RECEIVED
MAR 14 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

110.

INVOICED

DATE 3-14-05

INV. NO. 2005061275

MAR 04 2005

CHAMPLIN REFINING CO #3 GLATHART

29-11-17W
CSL SW SE

Contr. _____ ELLIS County

E 2098 Comm. 1-6-41 Comp. 1-20-41 IP 118 BOPD

Tops	Depth	Datum
ANH	1330	
LANS	3340	
ARB	3599	
TD	3628	

Casing
4" 3628

SO 3601-3627
Perf 48/3605-3624
Bail 5 BO/12 hrs
A/1000
Swb 8 BOPH: A/3000

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

