

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15841-00-00
Spot: SWSESE Sec/Twnshp/Rge: 36-17S-11W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: PATZNER A Well #: 7
County: BARTON Total Vertical Depth: 3246 feet

Operator License No.: 8653
Op Name: PETROLEUM TECHNOLOGIES, INC.
Address: 801 W. 47TH ST STE 412
KANSAS CITY, MO 64112

COND Size: 15.5 feet: 130
PROD Size: 5.5 feet: 3240 60 SX CMT
SURF Size: 7 feet: 3243 40 SX CMT

\$105⁵⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2005 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing parted.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2005 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech shot two holes. Perfs at 180' - 575' - 1375'.
Bottom was sanded off to 3170' and covered with 5 sxs cement using a dump bailer.
RIH with tubing 93' between 7" and 15 1/2" casing.
Pumped 75 sxs 60/40 pozmix to circulate cement to surface.
RIH with tubing to 1375' inside the 5 1/2" casing.
Pumped 120 sxs cement with 300# hulls to circulate cement up 5 1/2" casing and 7" casing.
Pulled tubing.
Tied onto 5 1/2" casing with a swedge and pumped 10 sxs 60/40 pozmix. Max. P.S.I. 600#. S.I.P 500#.
Tied onto 7" casing with a swedge and pumped 10 sxs 60/40 pozmix. Max. P.S.I. 300#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3243	3246		

RECEIVED
MAR 11 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 3-14-05
INV. NO. 2005061277

Form CP-2/3

MAR 08 2005

31

~~NO. 1~~
~~NO. 2~~

SPENCER & YARNELL

#7A PATZNER

36-17-11W

SE SE

Contr.

BARTON

County

E 1809

Comm. 8-1-38

Comp. 9-11-38

IP

2946 BOPD

Tops	Depth	Datum
ANHY	563	
LANS	2945	
ARB	3244	
TD	3246	

Casing

12" 250

7" 3241

SO&G 2945-50

SSO 298R-9R

SO & 7 RW, 3050-60

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS