

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20710-00-01
Spot: SENENE Sec/Twnshp/Rge: 15-10S-22W
4260 feet from S Section Line, 400 feet from E Section Line
Lease Name: GRIFFITH Well #: 2
County: GRAHAM Total Vertical Depth: 3770 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

PROD Size: 4.5 feet: 3768 w/150 sxs cmt
SURF Size: 8.625 feet: 211 w/150 sxs cmt

#122⁵³

Well Type: EOR UIC Docket No: E25810.1 Date/Time to Plug: 02/25/2005 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: PETE FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 230 sxs 604/0 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2005 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perf at 1220' w/200 sxs cement. Perf at 730' w/645 sxs cement.
Casing squeeze at 1193' - 1223' w/200 sxs cement.
Ran tubing to 1540' - top of fish - spotted 40 sxs cement with 150# hulls - got tubing stuck.
Pulled free - pulled all tubing out of hole and cleaned out tubing.
Ran tubing back in to 925' and circulated with 65 sxs cement with zero hulls.
Pulled all tubing and squeezed 4 1/2" casing with 10 sxs cement.
Max. P.S.I. 800#. S.I.P. 800#.
Tied to annulus and squeezed 50 sxs cement with 150# hulls.
Max. P.S.I. 400#. S.I.P. 200#.
Total of 165 sxs 60/40 pozmix - 10% gel and 300# hulls.

Perfs:

Top	Bot	Thru	Comments
3571	3714		

RECEIVED
MAR 11 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. MURFIN DRILLING-WATER.

Plugged through: TBG

District: 04

Signed Roger L. Moses (TECHNICIAN)

INVOICED
DATE 3-14-05
INV. NO. 2005061278

MAR 09 2005

A. SCOTT RITCHIE #2 GRIFFITH 15-10-22W
 412 UNION CENTER BLDG., WICHITA, KS. APP. C NE NE
 CONTR MURFIN DRLG. CTY GRAHAM

GEOL AL STUDE FIELD FAUL NE CONF

E 2279 KB c10/4/74 CARD ISSUED 3/13/75 IP P 65 BOPD, HW

API 15-065-20,710 LANS 3571 $\frac{1}{2}$ -74 $\frac{1}{2}$
 GR 410

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		1773	+ 506
B ANH		1813	+ 466
HEEB		3492	-1213
TOR		3513	-1234
LKC		3530	-1251
BKC		3765	-1486
LTD		3768	-1489
RTD		3770	-1491

8-5/8" 211/150SX, 4 $\frac{1}{2}$ " 3768/150SX
 DST (1) 3556-3577/30-45-30-45, REC
 305'OIL, 365'MCO, 65'OCWM, SIP
 626-626#, FP 65-260#
 DST (2) 3595-3610/30-30-30-30, REC 15'
 0 SP M, SIP 838-774#, FP 43-65#
 DST (3) 3608-25/30-45-30-45, REC 480'
 SW, SIP 860-774#, FP 43-238#
 DST (4) 3655-3740/30-30-30-30, REC 60'
 M, 120'WM, SIP 1200-1115#, FP 65-
 173#
 MICT - PF 3571 $\frac{1}{2}$ -74 $\frac{1}{2}$ (LANS), A 1000,
 FU 950'OIL/12HRS, T&R, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

15101010