



15-123-20001-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

August 22, 1971

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
8-26-71

Dear Sir:

Mr. Vaughn Thompson of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: H. C. Gillin

Complete Address: Box 914, Shawnee Mission, Kansas

Lease Name: Thierolf Well No. 1

Location: NW NW NE Sec. 31 Twp. 6 Rge. 6 (E)(W) X

County: Mitchell Total Depth 4275' Oil Well     

Gas Well      Input Well      SWD Well      OWWO  
D & A X Lost Hole     

Mr. Thompson was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/2 sack hulls to 250' and  
cement hole with 25 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10  
sacks cement. Bridge rathole and cement with 2 sacks cement.

INVOICED

Very truly yours,

DATE 8/30/71  
INV. NO. 4234-W

[Signature]  
Conservation Division Agent