



15-123-20002-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

November 3, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1969
CONSERVATION DIVISION
Wichita, Kansas
11-14-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Julius Ehrlich of Ehrlich Drilling Company has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Ehrlich Drilling Company

Complete Address: Wilson, Kansas 67490

Lease Name: R. File Well No. 1

Location: NW NW Sec. 34 Twp. 6 Rge. 6 (E) (W) X

County: Mitchell Total Depth 2868' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/4 sack hulls to 250' and
cement hole with 30 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

William J. Roman
Conservation Division Agent