

State of Kansas



15-123-20001-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

September 13, 1969

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 18 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 9-18-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Julius Ehrlich of Ehrlich Drilling Company has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Ehrlich Drilling Company

Complete Address: Wilson, Kansas

Lease Name: Thersof (Thierolf) Well No. 1

Location: NW NW NE Sec. 31 Twp. 6 Rge. 6 (E) (W) X

County: Mitchell Total Depth 3760' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Fill hole with heavy mud. Push plug to 300' and pump 25 sacks cement
through drill pipe at 300'. Pump 25 sacks cement through drill pipe at
200'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent