

State of Kansas



15-163-30184-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1966  
4-25-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. HARME of thoroughbred Dr. has this date requested permission to plug the following described well:

Mr. HARME guarantees payment of the plugging fee.

Operator's full Name: NATIONAL ASSOCIATED PETROLEUM INC

Complete Address: Fifth Floor Pitz Bldg, Tulsa, Okla.

Lease Name: Richard A. Wagner Well No. 1

Location: SE-SW-SE Sec. 32 Twp. 1e Rge. 17(E)(W) X

County ROOKS Total Depth 3235 Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. HARME was instructed to plug the well as follows:

Jett pitts circulate hole with heavy mud, set cementing plug at 540 ft.,  
and displace 30 sax cement thru drill pipe, heavy mud to 210 ft., set  
cementing plug and displace 20 sax cement thru drill pipe, heavy mud  
to 40 ft., set cementing plug, 1/2 sac hulls and 10 sax cement, cementing  
to base of cellar. Plug rat hole with two sax cement.

Very truly yours,

Geo Massey  
Conservation Division Agent