



15-163-20879-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1979

1-15-79
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Helberg of Helberg Drlg. has this

date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Two-Way Oil Co.

Complete Address: 407 S. Main, Plainville, Ks.

Lease Name: Dix Well No. 1

Location: NW NW SW Sec. 32 Twp. 6 Rge. (E)(W) 17

County: Rooks Total Depth 3165' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Helberg was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 600' thru drill

pipe. Heavy mud to 180' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

R. M. Massey
Conservation Division Agent