

State of Kansas



15-163-30181-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 4 1966
4-4-66
CONSERVATION DIVISION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Chas. Harre of Thoroughbred Drilling has this date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Co.

Complete Address: 502 Ritz Bldg. Tulsa, OKLA.

Lease Name: N.A. Riffel Well No. 2

Location: SE-NE-SE Sec. 31 Twp. 6 Rge. 17 (E)(W) X

County ROO KS Total Depth 3322 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Harre was instructed to plug the well as follows:

~~Jet pits circulate hole with heavy mud, set cementing plug at 540ft.,~~

~~and displace 20 sac cement thru drill pipe, heavy mud to 180ft., set cementing plug and displace 20 sac cement thru drill pipe, heavy mud~~

~~to 40 ft., set cementing plug, 1/2 sac hulls and 10 sac cement, cementing~~

~~to base of collar. Plug rat hole with two sac cement.~~

Very truly yours,

Leo Massey
Conservation Division Agent