



15-163-20493-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 7 1973

CONSERVATION DIVISION  
Wichita, Kansas

6-9-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fickle of Red Tiger Drlg. has this date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 Vickers KSB&T Bldg., Wichita, Ks.

Lease Name: Baughman Well No. 1

Location: SE SE NW Sec. 3 Twp. 6 Rge. (E)(W) 17

County: Rooks Total Depth 3235' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Fickle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 700' and displace  
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey  
Conservation Division Agent