

MAR 09 2005

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

CONSERVATION DIVISION KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WICHITA, KS

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Cabot Oil & Gas Corporation

Address: 600 17th Street, Ste. 900N, Denver, CO

Phone: (303) 226-9443 Operator License #: 6120

Type of Well: SWD Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3-3-05 (Date)

by: Jim Holland (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Glorietta Depth to Top: 1150' Bottom: 1170' T.D. 6535' Chase Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API Number: 15 - 175-00039-00-02

Lease Name: L. C. Schmidt (SWD)

Well Number: 1

Spot Location (QQQQ): - C-S/2 - S/2 - NE 2970 Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec. 26 Twp. 33 S. R. 34 East West

County: Seward

Date Well Completed: 4/20/51 9/9/60 Re-Entry

Plugging Commenced: 3-3-05

Plugging Completed: 3-4-05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Glorietta and Chase.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Drilled out cement to 814'. Tagged top of FG tbg @ 900'. (Baker Model D pkr. @ 913'. CIBP @ 1525'). Circ hole w/mud. RIH w/25 jts 2-7/8" tbg to 783'. Spot 20 sx cmt. Pull 7 jts to 600'. Pump 43 sx cmt. POOH. RIH w/1 jt tbg to 40'. Pump 8 sx cmt, circ to surface. POOH, cut off csg and capped 3' below surface. Plug @ 715'-815', 375'-600', 40' - surface.

Name of Plugging Contractor: Borderline Well Service License #: 7840


Address: P. O. Box 1043, Ulysses, KS 67880

Name of Party Responsible for Plugging Fees: Cabot Oil & Gas Corporation

State of Colorado County, Denver, ss.

Jay Vashler (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jay Vashler

(Address) 600 17th Street, Ste. 900N, Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 8th day of March, 20 05

My Commission Expires Notary Public My Commission Expires: 12-22-06