

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: Box 2528 Liberal KS 67905
Phone: (620)629-4200 Operator License #: 5447
Type of Well: Gas HI ^{KCC 3-15-05} Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic Protection, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-3-04 (Date)
by: Jim Holland (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chase Depth to Top: 2603 Bottom: 2718 T.D. 6394

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-175-21699-00-01
Lease Name: Hitch H
Well Number: 2
Spot Location (QQQQ): _____ - _____ - S/2-SE
1250 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 32 Twp. 32 S. R. 34 East West
County: Seward
Date Well Completed: 6-16-98 original ^{KCC 3-16-05}
Plugging Commenced: 12-28-04 ^{KCC 3-16-05}
Plugging Completed: 12-29-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1714	-
				5 1/2	2949	-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up jacks on 5 1/2. Showed cemented below 200 ft. CIBP+2sx cmt. from 2580 to 2560. Load 5 1/2 w/mud to 1750, mixed 25 sx 1750 to 1550, mud spacer to 500, mixed 60 sx cmt. 500 to 0 pres. up to 500 lb. Pres. up on annulus to 1000 lb. Capped 8 5/8 5 ft. below G.L.


Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS. 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kenny Andrews
(Address) 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

SUBSCRIBED and SWORN TO before me this 9th day of March, 2005
Anita Peterson My Commission Expires: Oct. 1, 2005
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
MAR 15 2005
KCC WICHITA *BW*