

RECEIVED  
MAR 14 2005  
KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

15.185.19073.00.00

**WELL PLUGGING APPLICATION FORM**

(PLEASE TYPE FORM and File ONE Copy)

API # Drilled 02/1960 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F.G. Holl Company, L.L.C. KCC LICENSE # 5056  
(owner/company name) (operator's)

ADDRESS 9431 E. Central, St. 100 CITY Wichita

STATE KS ZIP CODE 67206 CONTACT PHONE # (316) 684-8481

LEASE MANNING "A" WELL# 1-9 SEC. 9 T. 21S R. 11 (East/West)

NE - NE - NW SPOT LOCATION/Q000 COUNTY Stafford

4950 - 2970 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2970 - 4950 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 377' CEMENTED WITH 190sx SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3427' CEMENTED WITH 90sx SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3398' - 3401' Arbuckle

ELEVATION 1778' T.D. 3427' PBDT 3388' ANHYDRITE DEPTH 536'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, hulls, cement and plug according to KCC regulations.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# (620) 793-0915/(620) 786-5783

ADDRESS P.O. Box 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service KCC LICENSE # 31925  
(company name) (contractor's)

ADDRESS 401 West Main, Lyson, KS. 67554 PHONE # (620) 727-3410

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 03/11/2005 AUTHORIZED OPERATOR/AGENT: Loveness Mpanje  
(signature)

le/05

8/05

15.185 19073.00.00

WELL LOG

Date Commenced  
Date Completed

February 9, 1960  
February 19, 1960

F. G. Holl  
Manning #1 NE NE NW  
Section 9-21S-11W  
Stafford County, Kansas

ELEVATION 1778' KB

0' - 190'	Surface Sand
190' - 275'	Red Beds
275' - 511'	Red Beds
511' - 536'	ANHYDRITE
536' - 1350'	Shale & Shells
1350' - 1665'	Shale & Lime
1665' - 2200'	Lime & Shale
2200' - 2660'	Lime & Shale
2660' - 2800'	Lime
2800' - 2954'	Lime
2954' - 2958'	Shale - HEEBNER
2958' - 2973'	Lime & Shale
2973' - 2986'	Lime - TORONTO
2986' - 3079'	Shale - DOUGLAS
3079' - 3097'	Lime & Shale - IATAN
3097' - 3347'	Lime - LANSING
3347' - 3354'	CONGLOMERATE
3354' - 3373'	Shale - SIMPSON
3373' - 3376'	Sandstone
3376' - 3428'	Dolomite - ARBUCKLE

ANHYDRITE(base)	536	-1242
HEEBNER	2954	-1176
TORONTO	2973	-1195
DOUGLAS	2986	-1208
IATAN	3079	-1301
LANSING	3097	-1319
CONGLOMERATE	3347	-1569
SIMPSON	3354	-1576
ARBUCKLE	3376	-1598
RTD	3428	-1650

Surface Casing: Set 277' of  
8 t/8" used with 190 sacks  
cement, 2% gel, 2% calcium  
chloride

Production Casing: Set 3428'  
5 1/2" with 90 sacks pozmix  
1/2" Flowseal per sack

AFFIDAVIT

State of Kansas . . . . . County of Barton

I, Lewis O. Chubb, Geologist, do swear that the statements and  
matters herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

By: L. O. Chubb  
Geologist

Subscribed and sworn to before me on this 29th day of January, 1960

Clay E. Stinson  
Notary Public

My Commission Expires: June 24, 1963.

RECEIVED  
MAR 14 2005  
KCC WICHITA



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Holl, F.G., Company L.L.C.  
9431 E Central, Suite 100  
Wichita, KS 67206

March 18, 2005

Re: MANNING A #1-9  
API 15-185-19073-00-00  
NENENW 9-21S-11W, 4950 FSL 2970 FEL  
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888