

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Petroleum Technologies, Inc.
Address: 801 W. 47th, Suite 412, Kans. City, Mo. 64112
Phone: (816) 531 6904 Operator License #: 8653
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. 3250'

API Number: 15-009-15843-00-00
Lease Name: Patzner "A"
Well Number: 9
Spot Location (QQQQ): -W/2 - W/2 - SE
1320 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 36 Twp. 17 S. R. 11W East West
County: Barton
Date Well Completed: 6-1-40
Plugging Commenced: 3-7-05
Plugging Completed: 3-9-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				15-1/2"	180	None
				7"	3246'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Perforated casing @1500', 858' & 230'. Ran 60' of tubing down 7" & 15-1/2" & circulated 50 sacks cement, ran tubing down 7" to 1450', pumped 130 sacks w/300# hulls & circulated. Pulled tubing out, hooked onto 7" & circulated 35 sacks, pumped 15 sacks to squeeze, 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Petroleum Technologies, Inc.
State of Kansas County: Rice ss.

RECEIVED
MAR 18 2005
KCC WICHITA


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 16th day of March, 2005

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

B