

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: L-K Wireline, Inc.
 Address: PO Box 1188 Hays, KS 67601
 Phone: (785) 625-6877 Operator License #: 5453
 Type of Well: SWD EOR ^{KCC 3-21-05} ^{BEM} ^{RDMS CP 2/3} Docket #: E16334-001
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 2/28/05 (Date)
 by: Herb Deines (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
N/A Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-01537-00-01
 Lease Name: Bedard
 Well Number: #2 SWD
 Spot Location (QQQQ): C - NE - SW - NW
1650 Feet from North / South Section Line
660 Feet from East / West Section Line
 Sec. 18 Twp. 9 S. R. 18 East West
 County: Rooks
 Date Well Completed: 1/30/64 ^{original}
 Plugging Commenced: 2/25/05
 Plugging Completed: 2/28/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	3497	3950	8-5/8	215	----
Granite Wash	Water	3950	3960	5-1/2	3497	-----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg. to 3000', spotted 150 sx 60/40 poz-mix w/ 500# hulls, pulled tbg. to 1500' circulated cement w 100 sx 60/40 poz-mix w/300# hulls. Pulled tbg. Tied to annulus mixed 50sx 60/40 poz-mix @ 350#, shut in @ 100#. Mixed 25sx down 5-1/2 casing @ 500# Shut in @ 50#

Perfs @ 1475' and 850' 3 each


Name of Plugging Contractor: Allied Cementing, Inc. License #: 99996
 Address: PO Box 31, Russell, KS 67665-0031

RECEIVED
03-17-05
MAR 17 2005

KCC WICHITA

Name of Party Responsible for Plugging Fees: L-K Wireline, Inc.
 State of Kansas County, Ellis, ss.

Randy K. Longpré, President - L-K Wireline, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) [Signature]
 (Address) PO. Box 1188

SUBSCRIBED and SWORN TO before me this 15 day of March, 20 05
Charlotte Weber My Commission Expires: 12-28-07
 Notary Public

BW