

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mike Kelso Oil, Inc.
Address: P.O. Box 467 Chase, Kansas 67524
Phone: (620) 938-2943 Operator License #: 31528
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 3227'

API Number: 15-159-21,300-00-01
Lease Name: Kinemond
Well Number: 1
Spot Location (QQQQ): _____ SE _____ NE _____ SW _____
1550 Feet from _____ North / South Section Line
2120 Feet from East / West Section Line
Sec. 7 Twp. 18 S. R. 9 East West
County: Rice
Date Well Completed: 6-25-48 original well
Plugging Commenced: 3-15-05
Plugging Completed: 3-16-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	257'	None
				4-1/2"	3215'	1431

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3150' and 4 sacks cement. Cut casing loose @1431', pulled up to 1200', pumped 35 sacks cement w/100# hulls, pulled up to 850', pumped 35 sacks w/100# hulls, pulled up to 310' and circulated 130 sacks to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Mike Kelso Oil, Inc.

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 16th day of March, 2005

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
03-18-05
KCC WICHITA

B