

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Noble Petroleum, Inc.

Address: 3101 N. Rock Rd. Suite 125 Wichita, KS 67226

Phone: (316) 636-5155 Operator License #: 31389

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. <u>3262'</u>

API Number: 15-159, 0194900-00

Lease Name: Lansing JR

Well Number: 13

Spot Location (QQQQ): _____ SE SE SE

330 Feet from _____ North / ☒ South Section Line

330 Feet from ☒ East / _____ West Section Line

Sec. 25 Twp. 18 S. R. 8 ☐ East ☒ West

County: Rice

Date Well Completed: _____

Plugging Commenced: 3-7-05

Plugging Completed: 3-8-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	310'	None
				5-1/2"	3261'	1405

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3110' and 5 sacks cement. Put casing loose @1405', pulled up to 1050', pumped 150# hulls & 35 sacks cement, pulled up to 700', pumped 150# hulls & 35 sacks cement, pulled up to 360' & circulated 100 sacks cement to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Noble Petroleum, Inc.

State of Kansas County: Rice ss. _____

Mike Kelso

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____


(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 16th day of March

, 20 05

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202