

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

03-21-05
CP 2/3

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil D/H KCC 13 E.M. 3-22-05 RBDms CP 2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3/1/05 (Date)
by: Steve Durant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lower Morrow Depth to Top: 5088 Bottom: 5092 T.D. 5385
Lower Morrow Depth to Top: 5143 Bottom: 5147 T.D. 5385
Chester Depth to Top: 5247 Bottom: 5282 T.D. 5385

API Number: 15-081-21567-00-00
Lease Name: Frey A
Well Number: 1-18
Spot Location (QQQQ): 90'E - 97'N C - SW - NW
1883' Feet from North / South Section Line
750' Feet from East / West Section Line
Sec. 18 Twp. 27 S. R. 33 East West
County: Haskell
Date Well Completed: 2/28/05
Plugging Commenced: 3/1/05
Plugging Completed: 3/2/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Chester	saltwater	5247	5282	8-5/8"	1881'	none
Lower Morrow	sli oil, saltwater	5088	5147	5-1/2"	5366'	2076
Chase Group	gas	2615	3000			
Council Grove	gas	3000	3345			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP @ 5215', CIBP @ 5040', 2 sx cement on top, perfs at 3000' and 2950'; 70 sx 60/40 pozmix, 6% gel, left 275' in (balanced) csg
Gelled water behind, cut off 5-1/2" at 2076'. Pull out to 1917, spot 50 sx cement plug, pull up to 880', spot
40 sx cement plug, pull up to 44', circ. 25 sx cement. Done 8:45 p.m. Acid Services Ticket #9425
3/3/05-cement still at csg top.


Name of Plugging Contractor: Kerr Well Service, Inc. License #: 32722
Address: P.O. Box 184, Tyrone, OK 73951

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.

Charles Casey Coats (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]
(Address) 8100 E. 22nd St North, Bldg 300
Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 17th day of March, 20 05
Michelle D Henning My Commission Expires:
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bo