

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

CONSERVATION DIVISION

Lease Operator: Petroleum Development Corporation

Address: 3801 Carson Avenue Evans, CO 80620

Phone: (970) 506-9272 Operator License #: 33325

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2-2-2005 (Date)

by: Darrel Dipman (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Niobrara Depth to Top: 1532 Bottom: 1563 T.D. 1745

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-023-20301-00-00

Lease Name: Feikert 386

Well Number: 8-6-2

Spot Location (QQQQ): N-E-S-W

2900' Feet from North / South Section Line

3180' Feet from East / West Section Line

Sec. 8 Twp. 2 S. R. 41 East West

County: Cheyenne

Date Well Completed: 4-4-91

Plugging Commenced: 2-25-2005

Plugging Completed: 2-25-2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Ogallala Aquifer	Water	Surface	257'	7"	3-25-91	N/A
Niobrara	Gas	Surface	1700'	4.5"	3-29-91	N/A

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pump 20 sks 60/40 poz with 10% gel down 7" surface casing max pressure 250# shut in with 100#. Pump 85 sks 60/40 poz with 10% gel and 200# cotton seed hulls down 4.5" casing max pressure 700# shut in with 200#. Cut off casing 5' below ground level.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: N/A

Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Petroleum Development Corporation

State of Colorado County, Weld, ss.

Tom W. Roelfs (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Tom W Roelfs

(Address) RR1, Box 206 St. Francis, KS 67756

SUBSCRIBED and SWORN TO before me this 17 day of March, 2005

Danny Archer My Commission Expires: 11-26-05
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

ALLIED CEMENTING CO., INC.

Federal Tax I.D.# ~~44-1234567~~

RECEIVED
KANSAS CORPORATION COMMISSION
1906
MAR 21 1965
CONSERVATION DIVISION
WICHITA, KS

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

License #

Oakley

DATE 2-25-65	SEC. 8	TWP. 2	RANGE 4W	CALLED OUT	ON LOCATION 9:30 AM	JOB START 9:50 AM	JOB FINISH 10:30 AM
LEASE Forkert 386	WELL # 8-6-2	LOCATION St Francis 2W 19 1/2 W N 3/4			COUNTY Cherokee	STATE KS	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR _____

TYPE OF JOB Plug old hole

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 700# MINIMUM 100#

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 1532' - 1564'

OWNER same

CEMENT AMOUNT ORDERED
105 sks 60/40 Poz 10% Gel
200# Halls

COMMON @ _____

POZMIX @ _____

GEL @ _____

CHLORIDE @ _____

ASC @ _____

Halls 2 sks @ _____

HANDLING @ _____

MILEAGE _____

EQUIPMENT

PUMP TRUCK CEMENTER Dean

377-291 HELPER Andrew

BULK TRUCK

377 DRIVER Jarrod

BULK TRUCK

_____ DRIVER _____

REMARKS:

pump 20 sks down B side max press
250# shut in 100#
pump 55 sks down 4 1/2 csg w/
200# Halls max press 700#
shut in 200#

Thank you

CHARGE TO: Petroleum Development Corp

STREET 36621 Hwy 385

CITY Wray STATE CO ZIP 67078

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TOTAL _____

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____

EXTRA FOOTAGE @ _____

MILEAGE 100 miles @ _____

MANIFOLD @ _____

TOTAL _____

PLUG & FLOAT EQUIPMENT

@ _____

@ _____

@ _____

@ _____

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____