

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Bear Petroleum Inc.
Address: PO Box 438, Haysville, KS 67120
Phone: (316) 524-1225 Operator License #: 4419
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-20,380-00-00
Lease Name: Wilson
Well Number: 1
Spot Location (QQQQ): _____ - C - SE - NW
3300 Feet from North / South Section Line
3300 Feet from East / West Section Line
Sec. 27 Twp. 21 S. R. 7 East West
County: Rice
Date Well Completed: _____
Plugging Commenced: 03-10-05
Plugging Completed: 03-14-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	173	
				5 1/2	3416	1500'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3312', bailed 5 sacks of Portland, ripped 2600', 2000', left tension on, ripped at 2000', 1800', 1600', 1500', worked free.
Pulled to 1000', pumped 35 sacks, pulled to 550', pumped 35 sacks, pulled to 300', circulated with 105 sacks laid rest of pipe down.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 401 West Main, Lyons, KS 67554


Name of Party Responsible for Plugging Fees: Bear Petroleum Inc.
State of Kansas County, Sedgwick, ss.

R. A. Schremmer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) P.O. Box 438, Haysville, KS 67060

RECEIVED
MAR 22 2005
KCC WICHITA



SUBSCRIBED and SWORN TO before me this 21st day of March, 2005
Shannon Howland My Commission Expires: 3/10/08
Notary Public

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
03/17/2005	644

Bill To
Bear Petroleum, Inc. PO Box 438 Haysville KS 67060

P.O. No.	Terms	Lease Name
	net	Wilson #1

Description	Qty	Rate	Amount
Rig Time	23.5	135.00	3,172.50T
Trucking Floor	1	90.00	90.00T
Sand	5	35.00	175.00T
Ripping Pipe	4	140.00	560.00T
Water Truck	2	60.00	120.00T
Backhoe	3	65.00	195.00T
Phone Calls	1	10.00	10.00T
Clerical	1	10.00	10.00T
Wiping Rubber	1	15.00	15.00T
Fresh Water	1	10.00	10.00T
03-10-05 Rigged up pulled rods, went in.			
03-11-05 Pulled tubing, sanded bottom, loaded hole, dug cellar and pit. Tore head down, set floor, pulled slips, checked hole, sand at 3312', bailed 5 sacks of Portland, ripped 2600' and 2000', left on tension, went in.			
03-14-05 Ripped 2000', 1800', 1600', 1500', worked free, pulled to 1000', pumped 35 sacks, pulled to 550', pumped 35 sacks, pulled to 300', circulated with 105 sacks, laid rest of pipe down, tore down, loaded out, empty pit, filled pit and cellar in.			
Subtotal			\$4,357.50
Sales Tax (6.3%)			\$274.52
Total			\$4,632.02

RECEIVED
MAR 22 2005
KCC WICHITA