

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas


WELL PLUGGING RECORD

15-163-02663-00-00

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 16 Twp. 6 Rge. (E) 19 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE SW

Lease Owner: Veeder Supply & Development Co.

Lease Name: Brobst Well No. 1

Office Address: Cherryvale, Kansas

Character of Well (completed as Oil, Gas or Dry Hole): Dry

Date well completed: Oct. 6, 1947

Application for plugging filed: Oct. 6, 1947

Application for plugging approved: Oct. 6, 1947

Plugging commenced: Oct. 6, 1947

Plugging completed: Oct. 7, 1947

Reason for abandonment of well or producing formation:

If a producing well is abandoned, date of last production: 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....

Name of Conservation Agent who supervised plugging of this well: Mr. Kerr, Great Bend, Kansas

Producing formation..... Depth to top..... Bottom..... Total Depth of Well: 3650 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|-----------------------------|
| | | | | 8 5/8" | 252' | Cemented from top to bottom |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Put 10 mud in hole from 3650 feet to 250 feet. Put in bridge and 15 sacks of cement on bridge. Filled with 10' to 35 feet. Put in bridge and 10 sacks of cement on bridge. Filling hole up to base of collar. Cut off surface pipe at base of collar and filled with dirt.

OCT 15 1947
10-15-1947

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Veeder Supply & Development Company, P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Emmett C. Veeder

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY,
By: Emmett C. Veeder President
P. O. Box 201, Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of October, 1947


Leo Laurad
Notary Public.

My commission expires July 11, 1948

PLUGGING
FILE SEC. 16 T. 6 R. 19W
BOOK PAGE 138 LINE 29

15-163-02663-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for _____ Farm Brobst No. 1 Depth 3650'
 Contractor Veeder Supply and Development Co. Pipe 252' of 8 5/8 Gg. Cemented with 175 sacks
 Location Se Se Sw Sec. 16 Twp. 6 Range 19W
 Commenced 9-26-47 Completed 10-7-47 County Rooks State Kansas

| | | | |
|-------------------|------|------|-----|
| Surface soil | 0 | 40 | 40 |
| Sand, shale | 40 | 125 | 85 |
| Shale | 125 | 252 | 127 |
| Shale shells | 252 | 870 | 616 |
| Red bed | 870 | 880 | 10 |
| Sand shale | 880 | 985 | 105 |
| Pyrite sand | 985 | 1125 | 140 |
| Sand shale shells | 1125 | 1675 | 550 |
| Anhydrite | 1675 | 1740 | 65 |
| Red bed | 1740 | 1760 | 20 |
| Shale shells | 1760 | 2360 | 600 |
| Line shale | 2360 | 2450 | 90 |
| Shale shells | 2450 | 2620 | 170 |
| Line shale | 2620 | 2855 | 235 |
| Shale | 2855 | 2950 | 95 |
| Shale shells | 2950 | 3110 | 160 |
| Line shale | 3110 | 3335 | 225 |
| Line | 3335 | 3485 | 150 |
| Line shale | 3485 | 3565 | 80 |
| Sand | 3565 | 3575 | 10 |
| Shale sand | 3575 | 3581 | 6 |
| Line shale | 3581 | 3620 | 39 |
| Line | 3620 | 3622 | 2 |
| Granit wash | 3622 | 3650 | 28 |
| Total Depth | 3650 | | |

| | |
|--------------|------|
| | Tops |
| Topeka | 3107 |
| Lansing | 3335 |
| Conglomerate | 3611 |
| Granit wash | 3620 |

AFFIDAVIT

STATE OF KANSAS
MONTGOMERY COUNTY SS:

ESMETT C. VEEDER, of lawful age, being duly and solemnly sworn on oath says; I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state, that the above drilling log covering the Brobst # 1 Well in Section 16-6-19W Rooks County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT CO.

By: Essett C. Veeder
President

Subscribed and sworn to before me this 13 day of October 1947

Leslie Leonard
Notary Public

My Commission Expires: 7-11-48

PLUGGING
 FILE SEC 16 T 6 R 19W
 BOOK PAGE 138 LINE 29