


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

ROOKS

County. Sec. 16 Twp. 6S Rge. 19W (X) (W)

Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner K & E DRILLING, INC.
Lease Name DRYDEN 'B' Well No. 1
Office Address 719 Union Center Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed November 20 19 60
Application for plugging filed November 20 19 60
Application for plugging approved November 20 19 60
Plugging commenced November 20 19 60
Plugging completed November 20 19 60
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3662 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	206'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug #1 - 500' with 20 sacks cement through drill pipe
Plug #2 - 180' with 20 sacks cement through drill pipe
Built solid bridge at 40' plug with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1960
11-29-1960
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wayne L. Brinegar (employee of owner) or ~~owner of operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne L. Brinegar
Wayne L. Brinegar
K & E Drlg. - 719 Union Center Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 60

Wildalee Wind Notary Public.

My commission expires October 30, 1961



R

15-163-00781-00-00

DRILLER'S WELL LOG

OPERATOR: **K & E DRILLING, INC.**
719 Union Center Bldg.
Wichita, Kansas

WELL NAME: **#1 DRYDEN 'B'**
LOCATION: **C SW NW**
Section 16-6S-19W
ROCKS COUNTY, KANSAS

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: **November 12, 1960**

CASING RECORD: **8 5/8" @ 206 w/150 SX**

COMPLETED: **November 20, 1960**

ELEVATION: **2169 DF 2171 KB**

ROTARY TOTAL DEPTH: **3662'**

PRODUCTION: **D & A**

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface clay	30
Sand	85
Shale	850
Shale and sand	1250
Sand	1450
Red Bed	1735
Shale	1973
Shale and shells	2380
Lime and shale	2490
Shale and lime	2680
Lime	2830
Shale and lime	3020
Lime	3590
Lime and shale	3630
Lime	3662 RTD

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1960

CERTIFICATION CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of SEDGWICK } ss:

I, Wayne L. Brinsgar of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Wayne L. Brinsgar

Subscribed and sworn to before me this 28th day of November, 1960

Wayne L. Brinsgar

Wildalee Wind
Notary Public

My Commission expires: October 30, 1961

