

3 022699

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

15-207-1947700-00
CONTROL NO. 20040041

SW,NW,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

1718 feet from south section line

4722 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name & FEE FUND PLUGGING

Address

Lease/Well# APT NO. 30

County WOODSON

Well Total Depth 1000' feet

Production Pipe: 2" Size Feet 1000'

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00a.m. Day: 7 Month: 3 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT

HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO

CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND

OUTSIDE THE 2" CASING.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐TECHNICIAN
None

Operations Completed: Hour: 1:00p.m. Day: 7 Month: 3 2005

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8"

ANNULUS TO 525'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED

FROM THE 8" SURFACE CASING AT SURFACE. THE 1" WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 211 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

MAR 14 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO. 20) (THIS WELL WAS NO.30 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

Bm