

3 022695

15-207-19482-00-00

To:

API NUMBER CONTROL NO. 20040041

STATE CORPORATION COMMISSION

NE,SW,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

Wichita State Office Bldg. - PLUGGING SECTION

1062 feet from south section line

130 S. Market, Room 2078

4387 feet from east section line

Wichita, Kansas 67202

## TECHNICIAN'S PLUGGING REPORT

Lease/Well# APT NO. 80Operator License # 101County WOODSONOperator: STATE OF KANSAS Fee FundWell Total Depth 1000' feetName & FEE FUND PLUGGING

Production Pipe: \_\_\_\_\_ Size Feet \_\_\_\_\_

Address \_\_\_\_\_

Surface Casing: 12" Size Feet 12'AB oil well X Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

D &amp; A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICELic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 10:00AM Day: 25 Month: 2 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSIONPhone: 620-432-2300Were: THIS WAS AN OLD ABANDONED WELL CONTAINING NO SURFACE CASING ANDNO EVIDENT CASING. THE PLUGGING PROPOSAL WAS TO DRILL OUT THE WELL TO ASDEEP A DEPTH AS POSSIBLE AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLEFULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All X Part \_\_\_\_\_

TECHNICIAN

None \_\_\_\_\_

Operations Completed: Hour: 12:00P.M. Day: 25 Month: 2 2005Actual Plugging Report: 12' OF 12" SURFACE CASING WAS INSTALLED. THE WELLWAS DRILLED OUT TO 440'. AT THAT DEPTH IRON WAS ENCOUNTERED. 1" PIPE WASRAN INTO THE WELL TO 440'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENTCIRCULATED FROM SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WASFILLED FROM SURFACE. 214 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

MAR 10 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO. 80) ( THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP. )(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

B