

3 022693

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

15-207-19483-00-00
CONTROL NO. 20040044

NE,SW,SW 1/4

Sec/Twp/Rge S.34-T.26S.-R.16E.

1226 feet from south section line

4596 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Lease/Well#

APT NO. 7-I-C

County

WOODSON

Operator: STATE OF KANSAS Fee Fund

Well Total Depth

1000' feet

Name & FEE FUND PLUGGING

Production Pipe: 2"

Size Feet 1000'

Address

Surface Casing: 6"

Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. #

6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: 16 Month: 2 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

CIRCULATED THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All ☐

Part ☐

TECHNICIAN

None ☐

X ☒

Operations Completed: Hour:

4:00P.M. Day:

16 Month:

2

2005

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM

SURFACE. 31 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

03-02-05
MAR 2 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO. 18) (THIS WELL WAS NO. 7-I-C ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN