

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22, 177-00-09  
NE-NW-SE, Sec. 17, T 6 S, R 19 W E

2350 feet from N S section line  
1600 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Mc CLURG. Well # 1

Operator: LADD PETROLEUM CORP.  
Name & Address: BOX 520  
GREAT BEND, KANS.  
67530

County ROOKS

Well Total Depth 3710 feet 120.58

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BUFFALO DRILLING CO License Number TAG. # 55

Address 435 PAGE COURT, 220 WEST DOUGLAS, WICHITA, MO 67202

Company to plug at: Hour: 7:00 PM Day: 24th Month: NOV. Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO ROD RANDALL

(company name) BUFFALO DRILLING CO (phone) 316-265-9686

were: 8 5/8" 211 FT SP. CUL. #1/140 2 60/ Pozmix 2% GEL-3% CA-CL. (ALLIED)  
ORDER 200 50/ Pozmix 6% GEL-3% CA-CL - 1st CELLO FLAKE AND 8 5/8" PLUG.  
SPOT WITH DRILL STEM-TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS.  
EIV. 2172 - ANH. 1715 - ARBUCKLE @ 3625 FT.

Signed Mary Schmidt  
(TECHNICIAN) BOIC

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:00 PM Day: 24th Month: NOV Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 200 50/ Pozmix 6% GEL-3% CA-CL, 1st CELLO FLAKE AND 8 5/8" PLUG  
SPOTTED WITH DRILL STEM-TURNED HOLE OVER - HEAVY MUD BETWEEN PLUGS  
1st Plug @ 3600 FT #/20 5th ENT., 2nd Plug @ 1725 FT #/20 5th ENT.  
3rd Plug @ 1050 FT #/100 5th ENT #/1 CELLO FLAKE, 4th Plug @ 270 FT #/140 5th ENT  
5th Plug <sup>SOLID BRIDGE</sup> HULL'S- PLUG @ 40 FT #/10 5th ENT, 10 5th IN RAT HOLE (CIRCULAR)

Remarks: CEMENTED BY ALLIED CMT.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Mary Schmidt  
(TECHNICIAN) BOIC

INVOICED

DATE 12-28-83

INV. NO. 7236-W

STATE CORPORATION COMMISSION

REC. 5 1983  
12-05-1983  
CONSERVATION DIVISION  
Wichita, Kansas