

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23356-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 19-6S-19W
230 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: CARPENTER Well Number: 1-19
County: ROOKS Total Vertical Depth: 3613 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 213
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 10/01/2002 5:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Plugging Space all plugs with heavy drilling mud through drill pipe.
Method: 30' of Reagan sand tested and recovered 15' drilling mud.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/01/2002 7:45 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1725' w/25 sxs. Anhydrite 1696' - 1730'.
2nd. Plug at 1000' w/100 sxs. Dakota 697' - 997'.
3rd. Plug at 265' w/40 sxs. Surface pipe 213'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.


RECEIVED
OCT 10 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 10-11-02

INV. NO. 2003060628

Form CP-2/3

OCT 09 2002