

4-041600

8-16

15-163-22834-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: ~~15-163-22834-00-00~~

SW SE NW /4 SEC. 19, 06 S, 19 W
2970 feet from S section line
3630 feet from E section line

Operator license# 6278 Lease Buss 'A' well # 1

Operator: Anchor Bay Corporation County Rooks 119.63

Address: 1600 Stout Street Well total depth 3681 feet
Suite #1400 Conductor Pipe: 0 inch @ 0 feet
Denver, Colorado 80202 Surface pipe 8 5/8 Inch @ 348 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:00P.M. Day: 16 Month: August Year: 94

Plugging proposal received from: Bill Lauck

Company: Anchor Bay Corporation Phone: -

Were: 4 1/2" casing set @ 3680' w/150 sxs. cmt. Perf. @ 3636' - 3642'.
W.L.M. @ 3650'. Perf. @ 1736' with 600 sxs. halco-lite plus 50 sxs.
common cwc.

Ordered 170 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 400#

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 23 1994
08-23-1994
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:30P.M., Day: 16, Month: August, Year: 94

Actual plugging report: Hooked-up to 4 1/2" casing. Squeezed down
casing with 170 sxs. 60/40 pozmix - 10% gel plus 400# hulls. Max. 1000#.
Checked annulus with 400# P.S.I. Cement at surface.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X did not [] observe the plugging. Dennis L. Hamel

INVOICED
DATE AUG 29 1994
INV. NO. 41050

(agent)
Form CP-2/3