

4-060662

3-5

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,753 ⁰⁰⁻⁰⁰

SE SW NE /4 SEC. 03, 06 S, 21 W
2970 feet from S section line
1650 feet from E section line

Operator license# 31389

Lease White well # 1

Operator: Nobel Petroleum, Inc.

County Graham

Address: 3101 North Rock Road - #125
Wichita, Kansas 67202

Well total depth 3622 feet ^{117.72}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 304 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Duke Drilling Company, Inc. License# 5929

Address: Great Bend, Kansas 67530

Company to plug at: Hour: 9:30A.M. Day: 5 Month: March Year: 95

Plugging proposal received from: Dwayne Chishosm

Company: Duke Drilling Company, Inc. Phone:

Were: Order 190 sxs. 60/40 posmix - 6% gel - 1/4# flocele per. sack.
Space all plugs with heavy drilling mud through drill pipe.
Arbuckle not reached per drilling contractor.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:30A.M., Day: 5, Month: March, Year: 95

Actual plugging report:
1st. plug at 1775' w/25 sxs. cement - Anhydrite 1760' - 1792'
2nd. plug at 1110' w/100 sxs. cement - Dakota 808' - 1108'.
3rd. plug at 355' w/40 sxs. cement - Surface pipe to 304'.
4th. plug at 40' w/10 sxs. cement.
Rathole with 15 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 16 1995
CONSERVATION DIVISION
WICHITA, KS
3-16-95

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2208 GL

I did / did not X observe the plugging.

[Signature]

DH (agent)

Form CP-2/3

INVOICED

DATE: 3-23-95

INV. NO. 42443