

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21899-00-01
Spot: S2 Sec/Twnshp/Rge: 17-11S-17W
1380 feet from S Section Line, 2640 feet from E Section Line
Lease Name: HADLEY D Well #: 18
County: ELLIS Total Vertical Depth: 3480 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 3479 w/200 sxs cmt
SURF Size: 8.625 feet: 249 w/200 sxs cmt

113¹⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2005 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MIKE STANTON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 800# hulls.
Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
F.O. tool at 1419' w/400 sxs cement to surface.
CIBP at 3390'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2005 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2790'. Allied pumped 150 sxs 60/40 pozmix - 10% gel with 500# hulls.
Pulled tubing to 1425'. Allied pumped 125 sxs cement with 300# hulls.
Pulled tubing to 723'. Allied pumped 75 sxs cement. No circulation.
Pulled tubing - will run in and tag cement.
03-08-2005 - Tagged cement at 1300' with tubing.
Pulled one joint. Allied pumped 80 sxs 60/40 pozmix - 10% gel cwc.
PTOH. Squeezed with 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3372	3379		
3260	3266		
3004	3010		
2842	2850		

RECEIVED
KANSAS CORP. & CONSERVATION DIVISION
MAR 21 2005
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 3.22.05
NO. 2005061310

Form CP-2/3

MAR 17 2005

UNION PACIFIC RESOURCES
FT WORTH TX 76101-0007

17-11 -17W
C S/2

#18 HADLEY D OWWO

site: 6 N & 8-1/4 E OF HYACINTH KS

cty: ELLIS


API 15-051-21899

contr: UNKNOWN

field: BEMIS-SHUTTS

geol:

fr date 07/13/92	spd date 03/27/92	drig comp 03/27/92	card issued 07/13/92	last revised 07/13/92
---------------------	----------------------	-----------------------	-------------------------	--------------------------



ELV: 1871 KB, 1866 GL LOG
 tops.....depth/datum
 *ANH1101 +770
 *B/ANH.....1141 +730
 LANS.....3050 -1179
 ARB.....3370 -1499
 PBD.....3425 -1554
 RTD OLD3480 -1609
 *SAMPLE TOP

IP status:

OIL, P 4.5 BO & 201.5 BWPD, SHAW 2842-3010 OA, LKC
 3266-3270 , ARB 3412-3415 ,
 OLD INFO: OPERATOR WAS CHAMPLIN PETROLEUM
 CO, 18 HADLEY D, SPD 01/23/80 , 01/29/80 8-5/8" 249
 / 200 SX, 5-1/2" 3479 / 200 SX, OIL, P 18 BO & 427
 BWPD, ARB 3412-3415 , (CARD ISSUED 04/25/80)
 CONTR: RED TIGER DRLG
 GEOL: E H ELICH
 NO CORES OR DSTS
 MICT - CO, PF (ARB) 8/3430-3434, AC 250 GAL (15%),
 SQZ'D W/75 SX, PB 3425 TD, PF (ARB) 6/3412-3415, AC
 900 GAL (15%), SO, POP, P 18 BO & 427 BWPD, 3/4/80
 NEW INFO: FR 07/13/92 , REWORKED 03/27/92 DC
 03/27/92

COPYRIGHT 1992
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

UNION PACIFIC RESOURCES
FT WORTH TX 76101-0007

17-11 -17W
C S/2

#18 HADLEY D OWWO

MICT - CO, PF (LANS J) 3266-3270, (TOP LWR) 3004-3010, (TOP UPR) 2842-2850, ACIDIZED
 (15% FE - AMT NA) W/10% XYLENE, FLUSH W/80 B LEASE WTR, SO, T & R, POP, P 4.5 BO &
 201.5 BWPD (GR 28.2) 3/30/92, COMMINGLED W/ARB

HADLEY D