

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-22621-00-00  
Spot: SWNE Sec/Twnshp/Rge: 8-17S-11W  
4290 feet from S Section Line, 790 feet from E Section Line  
Lease Name: POPPELREITER Well #: 2  
County: BARTON Total Vertical Depth: 3328 feet

Operator License No.: 8653  
Op Name: PETROLEUM TECHNOLOGIES, INC.  
Address: 801 W. 47TH ST STE 412  
KANSAS CITY, MO 64112

PROD Size: 5.5 feet: 3323 125 SX CMT  
SURF Size: 8.625 feet: 256 200 SX CMT

#108<sup>16</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/10/2005 4:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: PETROLEUM TECHNOLOGIES, IN Phone: (816) 392-4234

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 10% gel with hulls.  
Plug while pulling casing.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 03/10/2005 6:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Sanded back to 3250' and spotted 5 sxs cement with dump bailer.  
Cut casing at 2300' but parted at 1340'.  
Mixed and pumped 95 sxs cement with 200# hulls.  
Pulled casing to 725' and pumped 40 sxs cement with 100# hulls.  
Pulled casing to 200' and circulated cement to surface with 65 sxs cement.  
Pulled casing with cement to surface.

Perfs:

Top	Bot	Thru	Comments
3323	3328		

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 21 2005  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE 3-22-05

TRV. NO. 2005061311

Form CP-2/3

MAR 17 2005

PETROLEUM ENERGY, INC.

710 ONE TWENTY BLDG.

WICHITA, KS 67202

#2 POPPELBEITER

8-17-11W

200'E, SW NE NE

CONTR WHITE & ELLIS DRLG.

CTY BARTON

GEOL

FIELD KRAFT-PRUSA

E 1868 KB CM 12/14/81 CARD ISSUED 2/4/82 IP P 106 BOPD, NW

API 15-009-22,621

ARB OH 3323-3328

+	+
+	+

SMP	TOPS	DEPTH	DATUM
HEEB		2930	-1062
TOR		2948	-1080
DOUG		2963	-1095
BR LM		3033	-1165
LANS		3050	-1182
ARB		3316	-1448
RTD		3328	-1460

8-5/8" 256/200sx, 5 1/2" 3323/125sx

DST (1) 3078-3118/30-30-30-30, REC 310' M, SIP 1037-1007#, FP 192-192/192-192#

DST (2) 3277-3321/30-30-30-30, REC 5' M W/SPKS O, SIP 42-32#, FP 32-32/32-32#

DST (3) 3276-3328/30-30-30-30, REC 195' HOCM, NW, SIP 1015-1000#, FP 92-92/115-123#

MICT - CO, (ARB OH), GSO IN BAILER, AC 250 GAL, SWB 16 BOPH, NW, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

43010EP