

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-06570-00-0001 *KCC BEM 3-21-05 per Scout Card*  
Spot: SWSENE Sec/Twnshp/Rge: 36-12S-16W  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease Name: AUSTIN LL Well #: 5  
County: ELLIS Total Vertical Depth: 3158 feet

Operator License No.: 31430  
Op Name: WHITE EAGLE RESOURCES CORP.  
Address: PO BOX 270948  
LOUISVILLE, CO 80027

L1 Size: 5 feet: 2987  
PROD Size: 6.625 feet: 3024  
SURF Size: 13 feet: 203

*\$102 6 4*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2005 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: RANDY WEIGEL Company: WHITE EAGLE RESOURCES CORP. Phone: (303) 665-1496

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Emergency plug with rig over the hole.  
Squeezed at 480' w/750 sxs cement; 565' w/140 sxs cement.  
Tubing stuck in the hole. TOF at 2872'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/16/2005 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Annulus full of cement.  
RIH with mill - got outside of pipe at 1130' - could not get past - decided to P&A.  
TIH with tubing to 1130' - mixed and spotted 65 sxs cement.  
Pulled up to 500' and circulated cement with 50 sxs cement.  
POOH. Swaged onto 6 5/8" and pumped 235 sxs cement with 200# hulls.  
Max. P.S.I. 500#. S.I.P. 200#.

Perfs:

RECEIVED  
KANSAS CORP. OF CONSERVATION  
MAR 21 2005  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

**INVOICED**

DATE 3-22-05  
INV. NO. 2005061313

MAR 17 2005

STANOLIND OIL & GAS

#5

AUSTIN

36-12-16W

SW SE NE

Contr.

ELLIS

County

E. 1877

Comm. 8-26-36

Comp. 11-9-36

IP

232 BOPD

Tops	Depth	Datum
ANHY	930	
TOP	2707	
DODGE	2945	
LANS	2995	
TD	3158	

Casing  
3024

Old Pot. 232 BOPD  
OWDD: 7-1-48


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

WASICEP