

15-23-19001-00-00

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **WILCOX OIL & GAS**

SEC. **23** T. **6** R. **9W**  
LOC. **NW SW NW**

FARM **Gish**

NO. **1**

TOTAL DEPTH **3634'**

COMM. **11-5-24**

SHOT OR TREATED

CONTRACTOR **G. M. Ashby**


ISSUED

COMP. **6-20-25** **RECEIVED**  
STATE CORPORATION COMMISSION

COUNTY **Mitchell**

KANSAS

MAR 20 1963



CONSERVATION DIVISION  
Wichita, Kansas

CASING

20 "	245'	10 "	1935'
15 1/2 "	522'	8 1/2 "	2697'
12 1/2 "	1230'	6 5/8 "	2900'
13		5 3/16 "	3270'

ELEVATION

PRODUCTION **Dry**

FIGURES INDICATE BOTTOM OF FORMATIONS

soil	15	lime	1600	blue shale	2950
black slate	40	shale light	1620	dark shale	3005
blue shale	45	lime	1630	lime	3010
black shale	50	light shale	1650	brown shale	3035
blue shale	100	lime	1705	yellow shale	3085
sand yellow lime HFW	245	black slate	1710	lime	3090
pyrites iron	249	shelly shale	1745	blue shale	3135
white sand	305	red rock	1755	pink shale	3163
Art. water 249-305'		lime	1765	red rock	3190
XXXXX red rock	308	blue shale cave	1790	blue shale	3195
water sand cave	315	lime	1800	gravel water	3217
shale	342	blue shale caving	1875	shale	3218
sand more wtr.	388	water sand	1885	lime	3230
lime	398	red rock	1890	black slate	3242
iron pyrites	412	blue shale	1970	brown lime	3255
blue shale	418	soft sand 3 BW	1985	lime	3313
black slate	422	blue shale	1970	lime	3430
blue shale lime	430	soft sand 3 BW	1985	blue shale	3441
lime	440	blue shale	2000	lime	3448
blue shale	450	broken lime	2030	green shale	3473
light shale	460	blue shale	2195	lime	3490
red rock	505	HFW @ 2135'		lime	3510
lime	508	white lime	2215	lime	3606
light shale	516	blue shale	2220	green shale	3616
red rock	600	lime	2227	lime	3634
blue shale	610	shale	2230	Total Depth	
red rock	660	lime	2240		
lime	665	shale	2245		
1 BW @ 665'		blue shale	2265		
red rock	730	bailing water @ 2265'			
brown shale	740	lime	2280		
blue shale	875	sand shale	2310		
lime	915	lime 2 BWPH	2335		
broken lime	935	shale	2345		
red rock	960	lime sandy	2410		
lime	980	white shale 5 BWPH	2440		
red rock	1005	blue shale 2460	XXXXX		
blue shale	1025	red rock	2480		
lime	1040	blue shale hole dry	2545		
red rock	1070	lime	2590		
lime	1090	broken lime	2630		
red shale caving	IN1140	shale HFW	2635		
lime	1150	lime	2673		
lime broken	1205	shale	2676		
lime broken	1270	lime	2697		
shale	1280	hard lime	2720		
lime	1335	lime	2770		
lime broken	1375	shale	2773		
red rock	1385	lime	2810		
broken lime	1435	shale	2815		
red rock	1455	lime	2827		
lime	1465	shale	2830		
red rock	1480	lime	2835		
lime	1505	shale	2840		
red rock	1530	lime	2860		
lime	1550	shale	2866		
red rock	1575	lime	2870		
		shale shells	2940		