

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-065-22,237 -00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR L.D. Drilling, Inc. OPERATORS LICENSE NO. 6039

ADDRESS RR 1 Box 183-B Great Bend, KS 67530 PHONE # (316) 793-3051

LEASE (FARM) Voss WELL NO. 1 WELL LOCATION SE SE SE COUNTY Graham

SEC. 6 TWP. 6 RGE. 21 ~~(S)~~ or (W) TOTAL DEPTH 3765 PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A  SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 258' CEMENTED WITH 160 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL \_\_\_\_\_

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? by operator  
(If not, explain) \_\_\_\_\_ to be filed

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11:35 a.m. 9-22-85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Bill Draney PHONE # (316) 793-8366

ADDRESS Box 823 Great Bend, KS 67530

PLUGGING CONTRACTOR Duke Drilling Co., Inc. LICENSE NO. 5929

ADDRESS Box 823 Great Bend, KS 67530 PHONE # (316) 793-8366

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Bill Draney  
STATE CORPORATION COMMISSION (Operator or Agent)

RECEIVED  
9-27-85  
SEP 27 1985

DATE: 9-22-85

DRILLER'S WELL LOG

DATE COMMENCED: September 15, 1985  
DATE COMPLETED: September 22, 1985

L.D. Drilling Inc.  
VOSS #1  
SE SE SE  
Sec. 6, T6S, R21W  
Graham County, Ks.

0 - 1860' Surface Soil, Shale, Sand  
1860 - 1892' Anhydrite  
1892 - 3438' Lime & Shale  
3438 - 3692' Lime  
3692 - 3734' Shale, Lime, Chert, Sand  
3734 - 3765' Dolomite  
3765' RTD

ELEVATION: 2202 K.B.

FORMATION DATA

Anhydrite 1860'  
Topeka 3212'  
Oreiad 3370'  
Heebner 3413'  
Lansing K.C. 3457'  
Base K.C. 3650'  
Conglomerate 3692'  
Arbuckle 3734'  
RTD 3765'

Surface Pipe: Set new  
8-5/8", 23# pipe @258'  
w/150 sacks 50/50 pozmix  
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 25 day of September 1985.

My comm. Expires:

4-29-86

Dorothy M. Hague  
Notary Public

Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 27 1985

CONSERVATION DIVISION  
Wichita, Kansas