

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-065-22,199-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR A. Scott Ritchie OPERATORS LICENSE NO. 5198

ADDRESS 125 N. Market, Suite 950, Wichita, KS 67202 PHONE # (316) 267-4375

LEASE (FARM) ROY VOSS "A" WELL NO. 1 WELL LOCATION SE SE SW COUNTY Graham

SEC. 6 TWP. 6S RGE. 21W (E) or (W) (W) TOTAL DEPTH 3800' PLUG BACK TO

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 260' CEMENTED WITH 190 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug @ 3756' w/20 sx; 2nd plug @ 1900' w/20 sx; 3rd plug @ 1150' w/100 sx + 15 sx Flocele; 4th plug @ 300' w/40 sx; 5th plug @ 40' w/10 sx; 10 sx in rat hole.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACC-1 FILED?
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 6-22-85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leo Swords PHONE # (913) 483-5372

ADDRESS Box 288, Russell, KS 67665

PLUGGING CONTRACTOR Murfin Drilling Company LICENSE NO. 6033

ADDRESS 250 N. Water, Suite 300, Wichita, KS 67202 PHONE # (316) 267-3241

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Robert A. Ramsey, Jr.

(Operator or Agent)
Robert A. Ramsey, Jr., Agent for Opr.
DATE: August 5, 1985

RECEIVED
STATE CORPORATION COMMISSION
AUG 7
8-7-85
CONSERVATION DIVISION
Wichita, Kansas


15-065-22199-00-00

WELL LOG

COMPANY A. Scott Ritchie
 125 N. Market, Suite 950
 Wichita, KS 67202
FARM ROY VOSS "A" **NO. 1**
RIG. NO. 16
TOTAL DEPTH 3800'
COMM. 6-15-85 **COMP.** 6-22-85
CONTRACTOR Murfin Drilling Company
 250 N. Water, Suite 300
 Wichita, KS 67202

SEC. 6 **T.** 6S **R.** 21W
LOC. SE SE SW

COUNTY Graham
 KANSAS



CASING
 20 10
 15 8-5/8" csg set @ 260' w/190 sx Common Quickset
 12 6
 13 5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	95'
Shale	261'
Sand & Shale	1900'
Anhydrite	1932'
Shale	2770'
Shale & Lime (RTD)	3800'

RECEIVED
 STATE CORPORATION COMMISSION


AUG 7 1985

CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas
 County of Sedgwick } ss:

I, Robert A. Ramseyer, Jr. of the Murfin Drilling Company

upon both the State and Federal records and foregoing is a true and correct copy of the log of the Roy Voss "A" #1 well.



Robert A. Ramseyer, Jr., Agent for Opr.
 August 19 85

Eleanor Hall NOTARY PUBLIC

My Commission Expires: 4-25-87